

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

NAME OF WORK:- Improvements to Roads and Drains Near Sridhar house area Amruthahalli in ward No. 7 Byatarayanpura, Kodigehalli sub division
Job code no : 007-16-000003

							ESTIMATED COST		3000000.00	
SI No	Description of work	Unit	No	L	B	D	QTY	Rate in Rs	Amount in Rs	
1	Removing BS Slab of drain and stacking. (P.No.25, I.No.5.32 of PW,P&IWD S.R 2014-15)						Sqm			
	Main Road (Sridhar house) Drains		2	43.00	1.65		141.90			
	Cable Road		2	96.00	1.65		316.80			
			2	76.00	1.65		250.80			
							709.50	58.32	41378.00	
	Basic Rate Rs.	54.00								
	Add 8% A.W Rs.	4.32								
	Total Rate Rs.	58.32								
2	Refixing stone slabs of drains and pointing in CM 1:3. (P.No.25, I.No. 5.33 of PW,P&IWD S.R 2014-15)						Sqm			
							Qty Same as I.No.1 (80%)	567.60	75.60	42911.00
	Basic Rate Rs.	70.00								
	Add 8% A.W Rs.	5.60								
	Total Rate Rs.	75.60								
3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick) (P.No.25, I.No.5.31.1 of PW,P&IWD SR 2014-15.)									
		Sqm								
							Qty Same as I.No.1 (20%)	141.90	639.36	90725.00
	Basic Rate Rs.	592.00								
	Add 8% A.W Rs.	47.36								
	Total Rate Rs.	639.36								
4	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.						Cum			
	(P.No.138, I.No.19.1 of PW,P&IWD S.R 2014-15)									
	Main Road (Sridhar house) Drains		2	43.00	0.60	0.30	15.48			
	Cable Road		2	96.00	0.60	0.30	34.56			
			2	76.00	0.60	0.30	27.36			
							77.40	75.60	5851.00	
	Basic Rate Rs.	70.00								
	Add 8% A.W Rs.	5.60								
	Total Rate Rs.	75.60								
5	KSRB5 25 providing and constructing non load bearing with cement concrete solid blocks with compressive strength not less than 3.5 newtown per sqmm with cement mortar 1:4 with block of size 40X10 X20cms (IXbXh) conforming to is:2185/1965 in superstructure including the cost of materials labour charges , scaffolding curing complete as specification (P.No.25 I.No.5.28 of PW,P&IWD S.R 2014-15)									
	Flagging Course		2	43.00	0.40		34.40			
	Cable Road		2	96.00	0.40		76.80			
			2	76.00	0.40		60.80			
							172.00	724.68	124645.00	
	Basic Rate Rs.	671.00								
	Add 8% A.W Rs.	53.68								
	Total Rate Rs.	724.68								

6	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.MORTH Specification No. 305.4.3 (P-144, Item No. 19.58 SR 2014-15)						Sqm	
	Main Road (Sridhar house)		1	43.00	5.30		227.90	
	Cable Road		1	96.00	6.90		662.40	
			1	76.00	6.90		524.40	
	Navynagar opp to jakkur junior col		1	60.00	5.00		300.00	
			1	87.00	5.00		435.00	
			1	122.00	5.00		610.00	
			1	175.00	5.00		875.00	
							3634.70	18.36
	Basic Rate Rs.	17.00						
	Add 8% A.W Rs.	1.36						
	Total Rate Rs.	18.36						66733.00
7	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (145, I.No. 19.64)14-15						Sqm	
	Main Road (Sridhar house)		1	43.00	5.30		227.90	
	Cable Road		1	96.00	6.90		662.40	
			1	76.00	6.90		524.40	
	Navynagar opp to jakkur junior col		1	60.00	5.00		300.00	
			1	87.00	5.00		435.00	
			1	122.00	5.00		610.00	
			1	175.00	5.00		875.00	
							3634.70	4.48
	Basic Rate	4.15						
	Area Weightage @ 8%	0.33						
	Total	4.48						16291.00
8	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 154 Item No. 20.18)14-15						Cum	
	Main Road (Sridhar house)		1	43.00	5.30	0.25	56.98	
	Cable Road		1	96.00	6.90	0.25	165.60	
			1	76.00	6.90	0.25	131.10	
	Navynagar opp to jakkur junior col		1	60.00	5.00	0.25	75.00	
			1	87.00	5.00	0.25	108.75	
			1	122.00	5.00	0.25	152.50	
			1	175.00	5.00	0.25	218.75	
	Basic Rate Rs.	1332.00					908.68	1438.56
	Add 8% A.W Rs.	106.56						
	Total Rate Rs.	1438.56						1307184.00
9	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 157, Item No. 21.6)14-15						Sqm	
	Main Road (Sridhar house)		1	43.00	5.30		227.90	
	Cable Road		1	96.00	6.90		662.40	
			1	76.00	6.90		524.40	
	Navynagar opp to jakkur junior col		1	60.00	5.00		300.00	
			1	87.00	5.00		435.00	
			1	122.00	5.00		610.00	
			1	175.00	5.00		875.00	
							3634.70	31.32
	Basic Rate Rs.	29.00						
	Add 8% A.W Rs.	2.32						
	Total Rate Rs.	31.32						113839.00

10	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25mm to 30mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 159, Item No. 21.20.2)14-15						Cum		
	Main Road (Sridhar house)	1	43.00	5.30	0.03	6.84			
	Cable Road	1	96.00	6.90	0.03	19.87			
		1	76.00	6.90	0.03	15.73			
	Navynagar opp to jakkur junior col	1	60.00	5.00	0.03	9.00			
		1	87.00	5.00	0.03	13.05			
		1	122.00	5.00	0.03	18.30			
		1	175.00	5.00	0.03	26.25			
						109.04	8475.84	924214.00	
	Basic Rate Rs.	7848.00							
	Add 8% A.W Rs.	627.84							
	Total Rate Rs.	8475.84							
11	KSRRB M800-13. Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (Page No. 178, Item No. 24.15) SR 2014-15						Sqm		
	Main Road (Sridhar house)	2	43.00	0.10		8.60			
	Cable Road	2	96.00	0.10		19.20			
		2	76.00	0.10		15.20			
						43.00	475.20	20434.00	
	Basic Rate Rs.	440.00							
	Add 8% A.W Rs.	35.20							
	Total Rate Rs.	475.20							
12	KSRRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2014-15						Cum		
	C.DS Jakkur Village Near Shobha Sapartment	1	8.00	1.80	0.90	12.96			
						12.96	176.04	2281.00	
	Basic Rate	163.00							
	Area Weightage @ 8%	13.04							
	Total	176.04							
13	KSRRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2014-15						Cum		
	C.DS Jakkur Village Near Shobha	1	8.00	1.80	0.15	2.16			
						2.16	5064.12	10938.00	
	Basic Rate	4689.00							
	Area Weightage @ 8%	375.12							
	Total	5064.12							

14	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2014-15					Cum		
	C.DS Jakkur Village Near Shobha	1x2	8.00	0.60	0.60	5.76		
						5.76	3836.16	22096.00
	Basic Rate	3552.00						
	Area Weightage @ 8%	284.16						
	Total	3836.16						
15	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaltons. Specification No. KBS 4.6.2 (P 15, I.No 4.28) SR-2014-15					Sqm		
	C.DS Jakkur Village Near Shobha	1	8.00	0.60		4.80		
	Side	2	6.00	0.23		2.76		
		2	1.80	0.23		0.83		
						8.39	236.52	1984.00
	Basic Rate	219.00						
	Area Weightage @ 8%	17.52						
	Total	236.52						
16	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15					Cum		
	C.DS Jakkur Village Near Shobha	1	8.00	1.80	0.23	3.31		
	Main Road (Sridhar house) Drains	2	43.00	0.45	0.10	3.87		
	Cable Road	2	96.00	0.45	0.10	8.64		
		2	76.00	0.45	0.10	6.84		
						22.66	5847.12	132507.00
	Basic Rate	5414.00						
	Area Weightage @ 8%	433.12						
	Total	5847.12						
17	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17 I.No. 4.46) SR-2014-15					Ton		
	C.DS Jakkur Village Near Shobha	1	8.00	1.80	0.23	3.31		
						3.31		
	3.31x100Kg/Cum					331.20		
						0.40	78351.84	31341.00
	Basic Rate	72548.00						
	Area Weightage @ 8%	5803.84						
	Total	78351.84						


18	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.109.I.No. 15.3) SR-2014-15					Sqm		
	C.DS Jakkur Village Near Shobha		1	8.00	0.60	4.80		
						4.80	92.88	446.00
	Basic Rate	86.00						
	Area Weightage @ 8%	6.88						
	Total	92.88						
19	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 5.00 Km (Page No.141)						Cum	
	Basic rate for haulage of materials as per item no.17.4 page 141) Rs. 2.00							
	Average weight of earth 1.28		Qty vide Item No.4+11		--	90.36	140.03	12653.00
	Basic Tate Lead Charges upto 2.00 Kms	62.20						
	2x1.28x2 =	5.12						
	Loading and unloading	67.32						
	Average Weight of earth 1.28 tone/kg for 6x1.20x2.00=12.00	5.39						
		72.71						
	Sub Total							2968451.00
20	Third party inspection charges 1%							29685.00
21	Miscellaneous & Rounding off							1864.00
						Toatl.Rs.		3000000.00

(Rupees:- Thirty Lakhs Only)

CERTIFICATE:

- 1 The work spot has been inspected me and the work is found to be necessary.
- 2 The estimate is prepared as per PW, P&IWTD S.R Bangalore circle for the year 2014-2015.
- 3 The Provisions made in the estimate are quite necessary and adequate.
- 4 The area comes with in the BBMP limits.


Junior Engineer
Ward No. 07


Assistant Executive Engineer
Kodigehalli Sub Division
BBMP


Executive Engineer
Byatarayanapura Division
BBMP

Administrative Approval

Accorded For **30.00 lakh R**
Head of A/C **P.3089**
CER NO : **25** Dt. **19.08.15**


 TA  CE (YNK)

Technical Sanction

Accorded For **30.00 lakh R**
Head of A/C **P.3089**
CER NO : **29** Dt. **21.08.15**

 TA  CE (YNK)

Name of works: Improvements Road and drains near
Sridhar House Area in Amruthahalli in
ward no 7 Kodigehalli Pub division
Est cost 30,000. Job no - 007-16-000003.



[Signature]

[Signature]